LAURION'S McLEOD INFILL DRILLING AT ISHKŌDAY INTERSECTS 4.00 m AT 1.16 g/t Au AND 3.44 g/t Ag, INCLUDING 1.70 m AT 2.13 g/t Au AND 5.67 g/t Ag, AND 3.50 m AT 0.97 g/t Au AND 1.86 g/t Ag, INCLUDING 0.50 m AT 6.01 g/t Au AND 7.00 g/t Ag

Highlights of Assays

LBX26-120 – McLeod Horizon, SRK Zone 5 – McLeod Zone

- **4.00 m grading 1.163 g/t Au and 3.44 g/t Ag** (135.00–139.00 m), **including 1.70 m grading 2.131 g/t Au and 5.67 g/t Ag** (135.70–137.40 m).
- **1.00 m grading 3.209 g/t Au and 3.80 g/t Ag** (15.30–16.30 m), **including 0.50 m grading 5.880 g/t Au and 6.30 g/t Ag** (15.80–16.30 m).
- **0.60 m grading 1.495 g/t Au and 1.40 g/t Ag** (107.60–108.20 m).

LBX26-119 – McLeod Horizon, SRK Zone 5 – McLeod Zone

- **0.70 m grading 6.370 g/t Au and 6.00 g/t Ag** (242.00–242.70 m).
- **1.10 m grading 2.174 g/t Au and 1.20 g/t Ag** (141.00–142.10 m).
- **2.30 m grading 0.673 g/t Au, 1.84 g/t Ag and 0.28% Zn** (222.00–224.30 m), **including 0.50 m grading 2.540 g/t Au, 5.90 g/t Ag, 0.27% Cu and 1.01% Zn** (223.30–223.80 m).
- **2.50 m grading 0.582 g/t Au and 1.10 g/t Ag** (225.50–228.00 m), **including 0.50 m grading 1.720 g/t Au and 2.40 g/t Ag** (225.50–226.00 m).
- **1.20 m grading 1.007 g/t Au, 5.41 g/t Ag and 6.62% Zn** (143.80–145.00 m), **including 0.50 m grading 1.910 g/t Au, 9.20 g/t Ag and 15.55% Zn** (143.80–144.30 m).
- **3.00 m grading 0.236 g/t Au and 15.33 g/t Ag** (245.00–248.00 m).

LBX26-118 – McLeod Horizon, SRK Zone 5 – McLeod Zone

- **3.50 m grading 0.969 g/t Au, 1.86 g/t Ag and 0.50% Zn** (162.50–166.00 m), **including 0.50 m grading 6.010 g/t Au, 7.00 g/t Ag and 3.01% Zn** (163.20–163.70 m).
- **1.00 m grading 1.637 g/t Au, 25.40 g/t Ag, 0.42% Cu and 1.99% Zn** (109.30–110.30 m), **including 0.50 m grading 3.050 g/t Au, 48.50 g/t Ag, 0.82% Cu and 3.95% Zn** (109.30–109.80 m).
- **1.50 m grading 0.928 g/t Au and 3.50 g/t Ag** (95.50–97.00 m).

TORONTO, Ontario — November 16, 2026 — LAURION Mineral Exploration Inc. (TSX-V: LME | OTC: LMEFF | FSE: 5YD) ("LAURION" or the "Company") is pleased to report assay results from drill holes LBX26-118, LBX26-119 and LBX26-120 from its 2026 Phase 1 diamond drilling program at its 100%-owned Ishkōday Gold and Polymetallic Project ("Ishkōday Project"), located approximately 220 km northeast of Thunder Bay and 28 km northeast of Beardmore, Northwestern Ontario.

Building on the drilling program, LAURION increased its planned Phase 1 drilling from 3,865 metres to 5,605 metres across 22 drill holes. The expanded program is being informed by SRK

Consulting's independent structural gap analysis of the A-Zone, which identified five priority target areas where additional drilling may address key gaps in the existing drill database and further strengthen the geological understanding of the A-Zone. LAURION is using this framework, together with ongoing drill results, to prioritize near-term drilling as it continues to systematically advance its exploration of the A-Zone, with the objective of validating its geological interpretation and supporting the evaluation of a potential maiden Mineral Resource Estimate ("MRE"). Additional targets, sequencing and timing remain subject to, among other things, ongoing results and available financing.

LBX26-118, LBX26-119 and LBX26-120 are infill holes targeting the "zones for infill" defined by SRK in Zone 5 of the McLeod mineralized horizon, one of the five priority areas identified in its gap analysis. Zone 5 is within the McLeod horizon, where wider spacing between historical drill holes has limited confidence in how mineralization connects. LBX26-119 was also stepped up-dip to further delineate the McLeod horizon, roughly halving the pierce-point distance from the Company's 2022 drill holes.

Cynthia Le Sueur-Aquin, President and CEO, commented: "*All three holes intersected gold, silver and zinc mineralization at multiple levels. LBX26-120 delivered the best combination of width and grade in this group:* ***4.00 metres grading 1.163 g/t Au and 3.44 g/t Ag, including 1.70 metres at 2.131 g/t Au and 5.67 g/t Ag, and intersected gold beginning at 15.30 metres down hole.***"

"*LBX26-119 returned seven separate intervals grading 1 g/t Au or better, including 0.70 metres at 6.37 g/t Au and 6.00 g/t Ag, together with an 8.30-metre polymetallic interval and a zinc-rich zone grading up to 15.55% Zn over 0.50 metres. LBX26-118 returned 6.01 g/t Au within a 3.50-metre interval and, higher in the hole, 48.50 g/t Ag over 0.50 metres.*"

"*SRK identified McLeod as one of five areas where, in their view, closer drill spacing matters most. With all three holes now reported, we believe that our geological team has the data it needs to model how this horizon is put together.*"

Summary of Drill Holes

Hole ID	Easting	Northing	Azimuth	Dip	Final Length (m)
LBX26-118	446162	5512507	133°	−45°	231
LBX26-119	446074	5512420	135°	−47°	276
LBX26-120	446145	5512364	133°	−45°	177
Total					**684**

Assay Results

LBX26-118 – McLeod Horizon, SRK Zone 5

LBX26-118 was drilled to infill the SRK Zone 5 area. It returned gold-silver-zinc mineralization at several levels, most notably a silver-rich polymetallic interval at 109.30–110.30 m and a gold-zinc interval at 162.50–166.00 m.

Hole ID	From (m)	To (m)	Core Length (m)	Au (g/t)	Ag (g/t)	Cu (%)	Zn (%)
LBX26-118	46.80	47.30	0.50	0.108	0.80	—	0.01
LBX26-118	62.80	63.30	0.50	0.161	0.25	—	0.02
LBX26-118	**95.50**	**97.00**	**1.50**	**0.928**	**3.50**	0.01	0.03
LBX26-118	**109.30**	**110.30**	**1.00**	**1.637**	**25.40**	0.42	**1.99**
Including	**109.30**	**109.80**	**0.50**	**3.050**	**48.50**	0.82	**3.95**
LBX26-118	113.40	114.20	0.80	0.152	0.25	—	0.04
LBX26-118	129.00	129.50	0.50	0.156	0.70	0.01	0.22
LBX26-118	138.00	138.50	0.50	0.280	0.80	0.02	0.44
LBX26-118	157.40	158.00	0.60	0.103	0.50	—	0.01
LBX26-118	160.00	161.00	1.00	0.233	1.20	—	0.03
LBX26-118	**162.50**	**166.00**	**3.50**	**0.969**	1.86	0.01	0.50
Including	**163.20**	**163.70**	**0.50**	**6.010**	**7.00**	0.04	**3.01**
LBX26-118	172.50	174.00	1.50	0.197	2.00	—	0.03
LBX26-118	178.00	179.00	1.00	0.188	0.70	0.01	0.03
LBX26-118	**180.00**	**180.50**	**0.50**	**0.916**	**6.00**	0.03	0.37
LBX26-118	194.60	196.20	1.60	0.315	2.27	—	0.21

LBX26-119 – McLeod Horizon, SRK Zone 5

LBX26-119 was stepped up-dip to tighten drill spacing on the McLeod horizon. Gold occurs as multiple discrete intervals down the hole, with seven intervals grading 1 g/t Au or better between 61.20 m and 242.70 m. A zinc-rich zone at 143.80–145.00 m, grading up to 15.55% Zn over 0.50 m, sits 1.70 m below a 1.10 m interval grading 2.174 g/t Au.

Hole ID	From (m)	To (m)	Core Length (m)	Au (g/t)	Ag (g/t)	Cu (%)	Zn (%)
LBX26-119	30.20	30.70	0.50	0.330	1.20	0.07	0.17
LBX26-119	31.80	32.50	0.70	0.246	1.50	0.01	0.31
LBX26-119	36.50	37.70	1.20	0.130	2.99	0.04	0.05
LBX26-119	41.00	41.50	0.50	0.211	0.25	—	0.02
LBX26-119	57.75	58.30	0.55	0.113	0.25	0.01	0.04
LBX26-119	61.20	61.70	0.50	**1.080**	1.30	0.01	0.02
LBX26-119	81.70	90.00	8.30	0.109	1.81	0.03	0.52
Including	85.00	87.90	2.90	0.220	2.78	0.06	**1.08**
LBX26-119	92.20	93.20	1.00	0.216	1.80	0.02	0.29
LBX26-119	104.50	106.30	1.80	0.613	1.02	0.01	0.09
Including	105.80	106.30	0.50	**1.595**	1.00	0.01	0.02

Hole ID	From (m)	To (m)	Core Length (m)	Au (g/t)	Ag (g/t)	Cu (%)	Zn (%)
LBX26-119	119.70	120.20	0.50	0.223	0.50	—	0.02
LBX26-119	125.70	126.70	1.00	0.176	0.90	—	0.04
LBX26-119	136.00	137.00	1.00	0.145	1.18	0.02	0.12
LBX26-119	139.00	140.00	1.00	0.101	0.25	0.01	—
LBX26-119	141.00	142.10	1.10	**2.174**	1.20	0.03	0.02
LBX26-119	**143.80**	**145.00**	**1.20**	**1.007**	**5.41**	0.04	**6.62**
Including	**143.80**	**144.30**	**0.50**	**1.910**	**9.20**	0.09	**15.55**
LBX26-119	**150.00**	**150.50**	**0.50**	**0.866**	**0.50**	—	0.03
LBX26-119	152.50	153.00	0.50	0.145	1.40	0.03	0.06
LBX26-119	169.30	170.50	1.20	0.363	0.56	0.01	0.02
Including	169.30	169.80	0.50	0.726	1.00	0.01	0.03
LBX26-119	184.50	188.00	3.50	0.163	1.56	0.05	0.37
Including	185.10	186.20	1.10	0.286	4.41	0.12	**1.07**
LBX26-119	206.40	207.40	1.00	0.266	5.60	0.03	0.76
Including	206.40	206.90	0.50	0.347	3.60	0.04	**1.49**
LBX26-119	**222.00**	**224.30**	**2.30**	**0.673**	1.84	0.07	0.28
Including	**223.30**	**223.80**	**0.50**	**2.540**	**5.90**	0.27	**1.01**
LBX26-119	**225.50**	**228.00**	**2.50**	**0.582**	**1.10**	0.02	0.03
Including	**225.50**	**226.00**	**0.50**	**1.720**	**2.40**	0.07	0.04
LBX26-119	230.00	231.00	1.00	0.158	0.50	—	0.07
LBX26-119	**242.00**	**242.70**	**0.70**	**6.370**	**6.00**	—	0.02
LBX26-119	**245.00**	**248.00**	**3.00**	**0.236**	**15.33**	0.02	0.09

LBX26-120 – McLeod Horizon, SRK Zone 5

LBX26-120 is the third infill hole in SRK Zone 5. It returned three intervals grading 1 g/t Au or better between 15.30 m and 139.00 m down hole. The strongest, 4.00 m grading 1.163 g/t Au and 3.44 g/t Ag from 135.00 m, includes 1.70 m grading 2.131 g/t Au and 5.67 g/t Ag.

Hole ID	From (m)	To (m)	Core Length (m)	Au (g/t)	Ag (g/t)	Cu (%)	Zn (%)
LBX26-120	**15.30**	**16.30**	**1.00**	**3.209**	**3.80**	0.03	0.11
Including	**15.80**	**16.30**	**0.50**	**5.880**	**6.30**	0.05	0.18
LBX26-120	**28.20**	**28.70**	**0.50**	**0.706**	0.25	—	0.01
LBX26-120	66.00	67.10	1.10	0.419	3.55	0.12	0.44
Including	66.50	67.10	0.60	0.578	4.50	0.18	0.80
LBX26-120	69.10	70.00	0.90	0.176	0.25	0.01	0.06

Hole ID	From (m)	To (m)	Core Length (m)	Au (g/t)	Ag (g/t)	Cu (%)	Zn (%)
LBX26-120	87.70	88.20	0.50	0.163	0.25	—	0.01
LBX26-120	**107.60**	**108.20**	**0.60**	**1.495**	1.40	0.01	0.03
LBX26-120	109.00	109.50	0.50	0.221	2.50	0.03	0.29
LBX26-120	117.00	117.50	0.50	0.327	1.40	0.01	0.51
LBX26-120	119.50	120.10	0.60	0.287	1.90	0.01	0.47
LBX26-120	**135.00**	**139.00**	**4.00**	**1.163**	**3.44**	0.06	0.24
Including	**135.70**	**137.40**	**1.70**	**2.131**	**5.67**	0.10	0.42

Note: All core lengths are drilled thicknesses; true widths have not yet been determined. Intervals are calculated using a nominal cut-off and may include internal dilution; "including" intervals are sub-intervals of higher grade contained within the reported interval. "—" indicates a value below the reporting threshold.

Sampling and QA/QC Protocols

All drill core is transported and stored inside the core logging facility located at the Ishkōday Project in Greenstone, Ontario.

LAURION employs an industry standard system of external standards, blanks and duplicates for all of its sampling, in addition to the QA/QC protocol employed by the laboratory. After logging, core samples were identified and then cut in half along the core axis in the same building and then zip tied individually in plastic sample bags with a bar code. Approximately five or six of these individual bags were then stacked into a "rice" white material bag and stored on a skid for final shipment to the laboratory. All core samples were shipped to the ALS Global Geochemistry facility in Thunder Bay, Ontario, where they were prepared, and the resulting pulps were analyzed by ALS Global Analytical Lab in North Vancouver, British Columbia. ALS is independent of LAURION. Samples are processed by 4-acid digestion and analyzed by fire assay on 50 g pulps and ICP-AES (Inductively Coupled Plasma – Atomic Emission Spectroscopy).

Over limit analyses are reprocessed with gravimetric finish. A total of 5% blanks and 5% standards are inserted randomly within all samples. 5% of the highest-grade assay result pulps were sent for re-assays. The remaining half of the core, as well as the unsampled core, is stored in temporary core racks at the core logging facility in Greenstone before being moved to the core storage facility at the Ishkōday Project.

QA/QC review of standards and duplicates indicates that the analytical results are reliable. One zinc standard adjacent to a high-grade zinc interval returned elevated values consistent with expected analytical behaviour following high-grade samples.

Qualified Person

The technical contents of this press release have been reviewed and approved by Dr. Trevor Boyd, Ph.D., P.Geo., a consultant to LAURION and a Qualified Person as defined by National Instrument 43-101 – *Standards of Disclosure for Mineral Projects* ("NI 43-101"). Dr. Boyd is independent of the Company within the meaning of NI 43-101.

About LAURION

LAURION Mineral Exploration Inc. is a mid-stage Canadian mineral exploration company, focused on advancing the 100%-owned Ishkōday Gold and Polymetallic Project in Northern Ontario.

The Ishkōday Project covers approximately 57 km² within the Beardmore–Geraldton and Onaman–Tashota Greenstone Belts and hosts a single 6.0 km by 2.5 km mineralized corridor. Historical and modern exploration programs have completed over 100,000 metres of drilling, confirming a large and evolving gold-rich polymetallic mineral system.

LAURION's strategy emphasizes disciplined, data-driven exploration, systematic technical advancement, integrated geological modelling, and responsible capital allocation. The Company is focused on strengthening geological confidence, expanding the scale of the mineral system, and positioning the project for a potential future MRE.

LAURION continues to evaluate opportunities that may enhance project development flexibility, including potential non-dilutive initiatives such as the evaluation of historical surface stockpile processing. The Company's objective is to build technical clarity, scale, and long-term project value before monetization, with the aim that future development decisions or strategic opportunities are supported by strong geological foundations and reduced execution risk.

Cynthia Le Sueur-Aquin, President and CEO of LAURION, is the Company's largest shareholder, holding 17,221,306 common shares, reflecting strong alignment between management and shareholders.

For Further Information, Contact:

LAURION Mineral Exploration Inc.

Cynthia Le Sueur-Aquin – President and CEO
Tel: 1-705-788-9186 Fax: 1-705-805-9256
Douglas Vass – Investor Relations Consultant

Email: info@laurion.ca
Website: http://www.LAURION.ca
Follow us on: X (@LAURION_LME), Instagram (laurionmineral) and LinkedIn

Caution Regarding Forward-Looking Information:

This press release contains forward-looking statements, which reflect the Company's current expectations regarding future events including with respect to LAURION's business, operations and condition, management's objectives, strategies, beliefs and intentions, the Company's ability to advance the Ishkōday Project and achieve the Company's strategic and technical objectives (within the above-stated timeframes, if at all), including with respect to the Company's expectations regarding the MRE, the nature, focus, timing and potential results of the Company's exploration, drilling and prospecting activities, including the Company's exploration program and planned exploration and drilling activities referenced in this press release, and the statements regarding the Company's exploration or consideration of any possible strategic alternatives and transactional opportunities, as well as the potential outcome(s) of this process, the possible impact of any potential transactions referenced herein on the Company or any of its stakeholders, and the ability of the Company to identify and complete any potential acquisitions, mergers, financings or other transactions referenced herein, and the timing of any such transactions.

The forward-looking statements involve risks and uncertainties. Actual events and future results, performance or achievements expressed or implied by such forward-looking statements could differ materially from those projected herein including as a result of a change in the trading price of the common shares of LAURION, the failure to obtain

the consents, permits and/or approvals from applicable governmental bodies, regulators and First Nations communities, required in connection with the Company's strategic and technical objectives, the risk that additional drilling and/or future results may not support the preparation of an MRE, the TSX Venture Exchange or any other applicable regulator not providing its approval for any strategic alternatives or transactional opportunities, the interpretation and actual results of current exploration activities, changes in project parameters as plans continue to be refined, future prices of gold and/or other metals, possible variations in grade or recovery rates, failure of equipment or processes to operate as anticipated, the failure of contracted parties to perform, labor disputes and other risks of the mining industry, delays in obtaining governmental approvals or financing or in the completion of exploration, as well as those factors disclosed in the Company's publicly filed documents. Investors should consult the Company's ongoing quarterly and annual filings, as well as any other additional documentation comprising the Company's public disclosure record, for additional information on risks and uncertainties relating to these forward-looking statements. The reader is cautioned not to rely on these forward-looking statements. Subject to applicable law, the Company disclaims any obligation to update these forward-looking statements. Readers are cautioned to not place undue reliance on the assay values reported in this press release. References to historical workings, historical exploration results and historical mining activities are provided for context only. Historical information may not be reliable and should not be interpreted as an indication of current mineral resources, mineral reserves or future exploration results.

NEITHER THE TSX VENTURE EXCHANGE NOR ITS REGULATION SERVICES PROVIDER (AS THAT TERM IS DEFINED IN THE POLICIES OF THE TSX VENTURE EXCHANGE) ACCEPTS RESPONSIBILITY FOR THE ADEQUACY OR ACCURACY OF THE CONTENT OF THIS NEWS RELEASE.